

Project Profile

Atterbury Boulevard Bridge Replacement (LPA)



QCI Group™



Year:
2009- 2010

Client:
City of Hudson

Location:
City of Hudson, Ohio

Project Scope:

Provided construction engineering support services for the removal and replacement of the Atterbury Boulevard Bridge Replacement in the City of Hudson. The project included the replacement of the existing 22-foot structure with a new 32-foot precast concrete arch, dewatering of site, demolition of existing bridge and pavement, installation of water and storm sewer, pile driving, foundations and installation of precast bridge including railings, and associated roadway approach work including storm sewer, curb and gutter, drive aprons, and new sidewalks. The new structure includes decorative railings and textured concrete for aesthetic appearance.

Project Services:

- Construction Engineering, Contract Administration, and on-site Inspection.
- General project oversight to monitor contract compliance.
- Served as liaison with contractors, owner, consultant, and utilities.
- Provided means and methods to aid in resolving conflicts and disputes.
- Reviewed contractor request for payments.
- Made recommendations to minor adjustments, substitutions.
- Reviewed and made recommendations to extra work requests.
- Coordinated all required materials testing.
- Provided LPA required services and as DBE monitor, monthly wage rates, certified payroll checks.
- Conducted biweekly progress meetings.
- Maintained submittal, RFI and extra work request logs.

Cost:
\$ 608 K